

Cameron Estates Community Services District

2023 Road Work Scope & Description

Project #711321- Bridge/Culverts - Rails and Pillars

Base Estimate. Contractor to price cost (per site) to restore these sites to their pre-disaster condition.

Site 1- (21-1) Mini Storage Bridge - 4040 Cameron Road. Cam 11 at SH7.

GPS start: 38.65624, -120.99411

- **Fence.** 48'L X 5'H, & 42' L X 5'H, bent and misaligned. Price to restore all to pre-disaster condition or replacement.
- **Columns.** 24 SF of brick (4 sides- 6 SF each side). 16"W X 54"H broken and washed out. Price to restore all columns.

Site 2- (21-1) Flying C Bridge 4501 Flying C Road. FlyC5. GPS start: 38.64217, -120.98879

- **Fence.** 1 of iron railing, 5/8" spindles on 5" centers, 20'L X 49"H. 2 of iron posts for fence. 4"L X 4"W X 52"H. 1 of iron railing, 5/8" spindles on 5"centers, 12'L X 49"H bent and misaligned. Price to restore or replace railings.